

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☐

OTHER

SINGLE
ZONE ☒MULTIPLE
ZONE ☐

c. NAME OF OPERATOR

Mosbacher Production Co. c/o Allen, Bludworth & Crouch

d. ADDRESS OF OPERATOR

P. O. Box 976 Casper, WY. 82602

e. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

1980' FWL 1980' FSL NE SW Sec. 24

At proposed prod. zone

Same

f. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately 6.5 miles north of Bluff, Utah

g. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

1980'

h. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

N/A

i. NO. OF ACRES IN LEASE

560

j. PROPOSED DEPTH

5780' KB

k. NO. OF ACRES ASSIGNED
TO THIS WELL

40

l. ROTARY OR CABLE TOOLS

Rotary

m. ELEVATIONS (Show whether DF, RT, GR, etc.)

4703' GR

n. APPROX. DATE WORK WILL START*

JUN 24 1981

o. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY
12-1/4"	9-5/8"	36#/Ft. K-55	400'	Sufficient to circulate to surface
8-3/4"	5-1/2"	15.5#/Ft. K-55	5780'	250 SX*

*Cement volume will be determined by hole size and caliper. Calculate after logging.

Drill 12-1/4" hole to 400' and run approximately 400' of 9-5/8" casing and cement to surface.

Drill 8-3/4" hole to 5780' and evaluate all hydrocarbon shows.

If the well is commercial, new 5-1/2", 15.5# casing will be run and cemented.

If the well is dry, a dry-hole marker will be set and the surface will be restored as outlined in the NTL-6. Cement plugs will be set according to U.S.G.S. instructions.

TEN POINT PLAN IS ATTACHED

N ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive one. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout reventer program, if any.

SIGNED

B. W. Allen

TITLE Petroleum Engineer

DATE June 22, 1981

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

Original Signed - John L. Price

TITLE

District Supervisor

DATE

2/1/81

CONDITIONS OF APPROVAL, IF ANY:

STIPULATIONS
ATTACHEDAPPROVED FOR A PERIOD
NOT TO EXCEED 1 YEAR.~~OPERATOR'S COPY~~

*See Instructions On Reverse Side


"APPROVAL TO PLUG GRANTED
WHILE DRILLING AND TESTING."

PROPOSED LOCATION
FEDERAL NO 24-1

NORTH 1930' &
EAST 1980' FROM S.W.
CORNER SECTION 24,
T39S, R21E, S.L.B. & M.,
SAN JUAN COUNTY, UTAH

SET REFERENCE
POINT (HUB)
ELEV = 4699'


IVAN
SCALE: 1" = 100'



CROSS-SECTIONS

HORIZONTAL
SCALE: 1" = 100'

VERTICAL
SCALE: 1" = 20'



POSED LOCATION

SHEET 1 OF 2

FEDERAL NO 24-1

IN SECTION 24, T39S, R21E,

S.L.B. & M., SAN JUAN COUNTY, UTAH

ELEVATIONS ARE BASED ON
S.W. CORNER SECTION 26,
T39S, R21E, S.L.B. & M.


(4691 - FROM U.S.G.S. TOPO,
BLUFF QUAD - 15 MINUTE)

N

BEARINGS ARE BASED ON SOLAR OBSERVATION


ELEVATIONS ARE BY
VERTICAL ANGLES
(W/ CORRECTION FOR
REFRACTION & CURVATURE)

SET REFERENCE POINT
(HUB) ELEVATION = 4699'



MAGNETIC
DECLINATION
15°


SET HUB @ CENTER OF
PROPOSED LOCATION
ELEVATION = 4703'



FOUND BRASSCAP SECTION
CORNER, S.W. CORNER, SECTION
24, T39S, R21E, S.L.B. & M.
(B.L.M. CADASTRAL SURVEY)

SCALE: 1" = 200'

TRANSIT, CHAIN & E.D.M. SURVEY
FOR: MOSBACHER PRODUCTION CO.
JUNE, 1981



RICHARD L. JOHNSTON
UTAH R.L.S. NO 4946

DRILLING PROGNOSIS

Mosbacher Production Co.
NE SW Section 24, T 39 S, R 21 E
San Juan County, Utah
Lease No. Utah 21253

1. SURFACE FORMATION

Entrada

2. GEOLOGICAL MARKERS - Estimated

Cutler	2600'
Hermosa	4700'
Ismay	5550'
Desert Creek	5780'

3. WATER, OIL AND GAS ZONES

Lower Ismay	5620' (Oil)
Desert Creek	5780' (Oil)

4. PROPOSED CASING SYSTEM (All New)

Depth	Size	Grade	Weight	Joint	Thread
0 - 400'	9-5/8"	K-55	36#/Ft.	ST&C	8Rd.
0 - 5780'	5-1/2"	K-55	15.5#/Ft.	LT&C	8Rd

Design Criteria: Tension 1.8, Collapse 1.125, Burst 1.0

5. PRESSURE CONTROL EQUIPMENT

Type:	b - 900 Series - Double Gate
Pressure Ratings:	3000 psi
Testing Procedure:	Equipment will be pressure tested prior to drilling out from under surface casing and operational checks will be made each trip thereafter and recorded.

6. MUD PROGRAM (Visual Monitoring)

Native mud will be used from surface to 300'. Water & Drill-Sol - Keep weight as low as possible - mud up at 2500' with nondispersed low solid Gel based drilling fluid.

Viscosity - 35-40 Weight - 8.8-9.0 Fluid loss - 10cc or less

A sufficient inventory will be stockpiled on location to maintain mud characteristics.

7. AUXILLARY EQUIPMENT

- 1) A kelly cock will be kept in the strings at all times.
- 2) Periodic checks will be made each tour of the mud system.
- 3) A stabbing valve will be kept on the derrick floor to be stabbed into the drill pipe whenever the kelly is not in the strings.
- 4) No float will be used.

8. EVALUATION PROGRAM

The well will be drilled to a total depth of 5780' through the Ismay into the Desert Creek. An IES-SP log will be run from the bottom of the surface casing to total depth. A Gamma Ray-Density-Neutron log will be run across the Desert Creek and Ismay formations. The logging program may change at the discretion of the well site geologist.

Drill Stem Test: As warranted by shows or loss.

Cores: None anticipated.

Stimulation

Breakdown will be with an acid treatment est. at 500 - 2000 gallons. Fracture treatments, if required, will be gelled water or oil-water emulsion. Volume will be determined following reservoir analysis. Storage tanks and stimulation equipment will be positioned in accordance with safe stimulation regulations.

A distance of 125 feet or more from frac tanks to bore hole and the same from frac trucks to the bore hole and tanks.

The U.S.G.S. will be notified prior to using any flammable liquid.

9. ABNORMAL CONDITIONS


It is not anticipated that abnormal temperatures, pressures or toxic gas will be encountered.

10. DRILLING ACTIVITY

Drilling will commence as soon as possible after approval depending on rig availability.

MOSBACHER PRODUCTION CO.
NE SW Section 24, T39N, R21E
San Juan County, Utah
Lease No. 21253

Typical Minimum BOP Specs (Schematic drawing)



Notes and Auxiliary Equipment

1. All lines, valves and fittings to be minimum 2"-3000# WP
2. All bolts to be installed and tight.
3. All crew members to be trained in and familiar with BOP equipment, accumulators, and procedures.
4. Hole to be kept full at all times.
5. (a) After nipping up, preventers will pressure tested at 1000 psi for 15 minutes before drilling out.
(b) BOP will be inspected and operated at least daily to insure good working order.
(c) All pressure and operating tests will be recorded on daily drilling report.
6. An upper kelly cock will be used at all times.
7. A drill pipe float will be available at all times for use when penetrating formations with anticipated abnormal pressures.
8. Mud system monitoring method: Visual
9. A 3000 psi WP full opening valve, properly subbed w/DP pin, will be available on the floor at all times.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

TYPE OF WORK
DRILL ☒ DEEPEN ☐ PLUG BACK ☐

TYPE OF WELL
OIL WELL ☒ GAS WELL ☐ OTHER ☐
SINGLE ZONE ☒ MULTIPLE ZONE ☐

NAME OF OPERATOR
Mosbacher Production Co. c/o Allen, Bludworth & Crouch

ADDRESS OF OPERATOR
P. O. Box 976 Casper, WY. 82602

LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)
At surface 1980' FWL 1980' FSL NE SW Sec. 24

At proposed prod. zone
Same

DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
Approximately 6.5 miles north of Bluff, Utah

DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any) 1980'

DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.
N/A

ELEVATIONS (Show whether DF, RT, GR, etc.)
4703' GR

5. LEASE DESIGNATION AND SERIAL NO.

Utah 21253

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Federal

9. WELL NO.

1-24

10. FIELD AND POOL, OR WILDCAT

~~Unleased~~ Wildcat

11. SEC., T., R., M., OR BLK.
AND SURVEY OR AREA

Sec. 24, T 39 S, R 21 E

12. COUNTY OR PARISH 13. STATE

San Juan Utah

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40

20. ROTARY OR CABLE TOOLS

Rotary

22. APPROX. DATE WORK WILL START*

JUN 24 1981

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	9-5/8"	36#/Ft. K-55	400'	Sufficient to circulate to surface
8-3/4"	5-1/2"	15.5#/Ft. K-55	5780'	250 SX*

*Cement volume will be determined by hole size and caliper. Calculate after logging.

Drill 12-1/4" hole to 400' and run approximately 400' of 9-5/8" casing and cement to surface.

Drill 8-3/4" hole to 5780' and evaluate all hydrocarbon shows.

If the well is commercial, new 5-1/2", 15.5# casing will be run and cemented.

If the well is dry, a dry-hole marker will be set and the surface will be restored as outlined in the NTL-6. Cement plugs will be set according to U.S.G.S. instructions.

TEN POINT PLAN IS ATTACHED

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS AND MINING

DATE: 10-2-81

BY: M. J. Minder

ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

SIGNED B. W. Allen TITLE Petroleum Engineer DATE June 22, 1981

(This space for Federal or State office use)

PERMIT NO. APPROVAL DATE

APPROVED BY John L. Price TITLE District Supervisor DATE 7/6/81

CONDITIONS OF APPROVAL, IF ANY:

STIPULATIONS ATTACHED APPROVED FOR A PERIOD NOT TO EXCEED 1 YEAR.

OPERATOR'S COPY

*See Instructions On Reverse Side

"APPROVAL TO PLANE GRANTED WHILE DRILLING AND TESTING."

Must have
st of Utl
approval
prior to
Plugging

PROPOSED LOCATION

FEDERAL NO 24-1

IN SECTION 24, T39S, R21E,

S.L.B. & M., SAN JUAN COUNTY, UTAH

ELEVATIONS ARE BASED ON
S.W. CORNER SECTION 26,
T39S, R21E, S.L.B. & M.


(4691 - FROM U.S.G.S. TOPO,
BLUFF QUAD - 15 MINUTE)

N

BEARINGS ARE BASED ON SOLAR OBSERVATION

ELEVATIONS ARE BY
VERTICAL ANGLES
(W/ CORRECTION FOR
REFRACTION & CURVATURE)

SET REFERENCE POINT
(HUB) ELEVATION = 4699'



MAGNETIC
DECLINATION
15°


SET HUB @ CENTER OF
PROPOSED LOCATION
ELEVATION = 4703'

23 24
26 25


FOUND BRASSCAP SECTION
CORNER, S.W. CORNER, SECTION
24, T39S, R21E, S.L.B. & M.
(B.L.M. CADASTRAL SURVEY)

SCALE: 1" = 200'

TRANSIT, CHAIN & E.D.M. SURVEY
FOR: MOSBACHER PRODUCTION CO.
JUNE, 1981



RICHARD L. JOHNSTON
UTAH R.L.S. NO 4946



and Town Ship Plat

EXHIBIT #1

30	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6
12	7	8	9	10	11	12	7
13	18	17	16	15	14	13	18
24	19	20	21	22	23	24 Federal 1-24	19
25	30	29	28	27	26	25	30
36	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6

KINTZEL BLUE PRINT CO., P. O. Box 741, Casper, Wyoming

Sec. 23, T 39 S, R 21E R. C. Anderson 1-22 D&A

Sec. 24, T 39 S, R 21 E, Mosbacher Fed. 1-24 (Proposed)

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☐ other Wildcat
well well2. NAME OF OPERATOR
Mosbacher Production Company3. ADDRESS OF OPERATOR Casper, WY
c/o Allen, Bludworth & Crouch P.O. Box 976

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)

AT SURFACE: 1980 FWL 1980' FSL

AT TOP PROD. INTERVAL:

AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE
REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐☐
☐
☐
☐
☐
☐
☐
☐

(other) Addition to A.P.D.

LEASE
Utah 21253

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Federal

9. WELL NO.

1-24

10. FIELD OR WILDCAT NAME

Wildcat

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Sec 24 - T39S-R21E

12. COUNTY OR PARISH 13. STATE

San Juan

Utah

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
703 GR.

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

RECEIVED
JUL 10 1981
DIVISION OF
OIL, GAS & MINING

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Operator proposes to change casing program to one of 3 alternate proposals listed to protect water sands above 1600 feet. Proposal selected will depend on data revealed by drilling and/or logging.

(1) Set 200' 13-3/8" 48# casing and cement to surface. Set 9-5/8", 36# intermediate casing at 1600'. Use sufficient cement to ~~cover water sands~~. *circulate*(2) Set 1600 feet of 9 5/8", 48# surface casing, cement to surface. *to surface*

(3) Run cement stage collar in 5 1/2" production casing below 1600 feet.

Cement casing with two stages. Second stage sufficiently large to ~~cover water sands~~. *circulate to surface.*

RECEIVED

JUN 29 1981

Subsurface Safety Valve: Manu. and Type

U. S. GEOLOGICAL SURVEY
DURANGO, COLO.

Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED

B.W. Allen

TITLE Petroleum Engineer DATE 6/25/81

Original Signed - John L. Price

(This space for Federal or State office use)

District Supervisor

APPROVED BY

TITLE

DATE

7/6/81

CONDITIONS OF APPROVAL, IF ANY:

Blind water

No Card file

DIVISION OF OIL, GAS AND MINING

PLUGGING PROGRAM

NAME OF COMPANY: Mosbacher Production Co. Dick Lauters 678-3231

WELL NAME: Federal #1-24

SECTION SW 24 TOWNSHIP 39S RANGE 21E COUNTY San Juan

VERBAL APPROVAL GIVEN TO PLUG AND ABOVE REFERRED TO WELL IN THE FOLLOWING MANNER:

TOTAL DEPTH: 5890'

CASING PROGRAM:

13 3/8 @ 205' cement to surface
9 5/8 @ 1768 cement to surface
8 3/4 @ openhole TD

FORMATION TOPS:

Chinle- behind casing
Cutler- 2602
Hermosa- 4670
Ismay- 5536-5630
Black Sh.- 5700
Desert Creek- 5735-5837

PLUGS SET AS FOLLOWS:

- 1) 5890-5470
- 2) 4770-4570
- 3) 2700-2500 displace with freshwater
abandonment mud
- 4) 1820-1720
- 5) 50-surface.

DST:

- 1) 5616-96 (10' of mud)
- 2) 5786-5890 (366' of mud)

No cores, no water encountered,
no shows.

Place 9.4#, 55 vis fresh water gel based
abandonment mud between plugs; clean, restore
and regrade site, erect regulation dryhole
marker.

DATE 8-17-81

SIGNED

M.T.M.

M.T. Minder

CC: Mosbacher Production Co.

**** FILE NOTATIONS ****

DATE: Sept. 29, 1981

OPERATOR: Mosbacher Production Co.

WELL NO: Federal #1-24

Location: Sec. 24 T. 39S R. 21E County: San Juan

File Prepared: ☒

Entered on N.I.D: ☒

Card Indexed: ☒

Completion Sheet: ☒

API Number 43-037-30720

CHECKED BY:

Petroleum Engineer: M. J. Minder 10-2-81

Director: _____

Administrative Aide: ok as Per Rule C-3,

APPROVAL LETTER:

Bond Required: ☐

Survey Plat Required: ☐

Order No. _____

O.K. Rule C-3 ☐

Rule C-3(c), Topographic Exception - company owns or controls acreage within a 660' radius of proposed site ☐

Lease Designation Fed

Plotted on Map ☐

Approval Letter Written ☐

Hot Line ☐

P.I. ☐

October 2, 1981

Mosbacher Production Co.
P. O. Box 976
Casper, Wyoming 82602

RE: Well No. Federal #1-24,
Sec. 24, T. 39S, R. 21E,
San Juan County, Utah

Insofar as this office is concerned, approval to drill the above referred to oil well is hereby granted in accordance with Rule C-3, General Rules and Regulations and Rules of Practice and Procedure.

Should you determine that it will be necessary to plug and abandon this well, you are hereby requested to immediately notify the following:

MICHAEL T. MINDER - Petroleum Engineer
Office: 533-5771
Home: 876-3001

Enclosed please find Form OGC-8-X, which is to be completed whether or not water sands (aquifers) are encountered during drilling. Your cooperation in completing this form will be appreciated.

Further, it is requested that this Division be notified within 24 hours after drilling operations commence, and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-037-30720.

Sincerely,

DIVISION OF OIL, GAS AND MINING



Michael T. Minder
Petroleum Engineer

MTM/db
CC: USGS



A GEOSCIENCE EXTENSION OF XCO

910 Sixteenth Street, #522, Denver, Colorado 80202 (303) 893-8138

RECEIVED
OCT 13 1981

DIVISION OF
OIL, GAS & MINING

MOSBACHER

FEDERAL 1-24

SECTION 24 T39S R21E

SAN JUAN COUNTY, UTAH

CONFIDENTIAL

GEOLOGIST: Chuck Hargrave
GX Consultants

TABLE OF CONTENTS

	<u>PAGE</u>
Resume	1
Summary and Conclusions	3
Formation Tops	4
Daily Chronology	5
Mud Record	6
Bit Record	7
Drilling Functions	7
Drill Stem Test #1	8
Drill Stem Test #2	9
Schlumberger Log Strips	10
Lithology	13

RESUME

OPERATOR: Mosbacher

WELL NAME & NUMBER: Federal 1-24

LOCATION: Section 24 T39S R21E

COUNTY: San Juan

STATE: Utah

SPUD DATE: July 21, 1981

COMPLETION DATE (TD): August 15, 1981

ELEVATIONS: 4,703' GL 4,716' KB

TOTAL DEPTH: 5,878' LOGS 5,890' DRLR

CONTRACTOR: Arapahoe

RIG: #6

TYPE RIG: --

PUMPS: #1 15" x 5½"
#2 12" x 5½"

GEOLOGIST: Chuck Hargrave

ENGINEER: --

TOOL PUSHER: Roy Shepard

TYPE DRILLING MUD: LSND

MUD COMPANY: Mancos Mud Company

MUD ENGINEER: Jeff Armstrong

HOLE SIZES: 12¼" Surface - 1,795'
8-3/4" 1,795' - 5,891'

CASING: 9-5/8" Surface To 1,795'

MUD LOGGING BY: Analex

TYPE UNIT: Standard 2-Man

CORE INTERVALS: None

DST DEPTHS: #1 5,616' - 5,695'
#2 5,792' - 5,890'

RESUME (CONTINUED)

DST COMPANY:	Halliburton
ELECTRIC LOGS BY:	Schlumberger
TYPE LOGS RUN:	FDC, CNL 1,712' - 5,878' I-SFL 3,848' - 5,878' CYBERLOOK 5,500' - 5,867'
LOGGING ENGINEER:	Julio Batista
BOTTOM FORMATION:	Akah (Shale)
WELL STATUS:	Plugged and Abandoned

SUMMARY AND CONCLUSIONS

The Mosbacher Production Company Federal 1-24 of San Juan County, Utah was spudded on July 21, 1981 and drilled to a total depth of 5,890' (driller), 5,878' (Schulumberger), penetrating the Akah Zone, of the Pennsylvanian Paradox Formation. The primary objective was the Lower Ismay Zone with the secondary objective being the Desert Creek Zone, both of the Paradox Formation.

In the Lower Ismay a drilling break occurred at 5,676' - 5,682' in a dolomite, whereas drill rate increased from 8 min/ft to 5 min/ft. A gas kick from 10 units to 80 units was also observed in this interval. A Drill Stem Test of this interval along with Electric Logs was evaluated, resulting in porosity and permeabilities being too low for hydrocarbon production.

In the Desert Creek a drilling break occurred at 5,810' to 5,832' in a dolomite, whereas drill rate increased from 5 min/ft to 2 min/ft. Gas kicks were observed at this interval of 100 and 230 units, from a background of 20 units. A Drill Stem Test along with electric log evaluations showed porosity and permeability very low.

Consequently, the hole was plugged and abandoned according to federal regulations.

FORMATION TOPS

FEDERAL 1-24
KB 4,716

<u>FORMATION</u>	<u>DEPTH</u>	<u>SUBSEA OR DATUM</u>
Cutler	2,600	+2,116
Hermosa	4,694	+ 22
Ismay	5,536	- 820
Lower Ismay	5,630	- 914
B Shale	5,710	- 994

DAILY CHRONOLOGY

1981 DATE	12:01 A.M. DEPTH	24 HOUR FOOTAGE	DAILY RECORD
7/29	2,190	--	Drilling.
7/30	2,610	420	Drilling, Trip for Bit #2.
7/31	2,902	292	Drilling, Trip for plugged jets in bit.
8/1	3,066	164	Trip cont., Drilling.
8/2	3,350	284	Drilling, Work on Power Plant.
8/3	3,678	328	Drilling.
8/4	3,795	117	Drilling, Trip for Bit #4.
8/5	4,063	268	Drilling, Work on #1 Pump.
8/6	4,264	201	Drilling, Work on pumps.
8/7	4,414	150	Drilling, Trip for pipe washout.
8/8	4,640	226	Drilling.
8/9	4,824	184	Drilling, Work on pumps.
8/10	5,032	208	Drilling.
8/11	5,141	109	Drilling, Trip for Bit #5.
8/12	5,322	181	Drilling, Work on #1 Pump.
8/13	5,526	204	Drilling #1.
8/14	5,695	169	Trip for DST #1.
8/15	5,695	0	Strap out run DST #1, Trip in drilling.
8/16	5,891	196	Strap out for DST #2.
8/17	5,891	0	Run DST #2, Circulate Run Logs, Start plugging procedures.

100

ON

[illegible]

BIT RECORD

BIT NO.	MAKE	TYPE	SIZE	DEPTH IN	DEPTH OUT	FOOTAGE	HOURS
1	STC	F-2	12½	Surface	1,800	1,800	39
2	HTC RR	J-22	8-3/4	1,800	2,290	490	23½
3	STC RR	F-2	8-3/4	2,290	2,899	609	34
4	HTC	J-22	8-3/4	2,899	3,795	896	80
5	STC	F-2	8-3/4	3,795	5,114	1,319	151½
6	HTC	J-33	8-3/4	5,114	5,695	584	74½
7	STC	F-3	8-3/4	5,695	5,891	196	20

DRILLING FUNCTIONS

DEPTH	WOB	RPM	PP	DEVIATION
2,060	40,000	50	1,200	¼°
2,300	40,000	55	1,025	¼°
2,600	40,000	55	1,050	¼°
2,870	40,000	55	1,100	¼°
2,901	40,000	60	1,100	½°
3,000	40,000	55	1,050	½°
3,600	40,000	55	1,100	½°
3,840	40,000	55	900	½°
4,690	48,000	55	1,200	3/4°
5,000	46,000	52	1,200	3/4°
5,100	38,000	55	1,000	1°
5,158	30,000	50	600	1°
5,178	45,000	60	1,000	1°
5,520	45,000	60	1,100	1°
5,660	46,000	60	800	1°
5,695	40,000	60	1,100	1°

DRILL STEM TEST #1

Formation: Lower Ismay
Interval: 5,616' to 5,695'
Reason For Test: Gas Kick And Drill Break
Type Test: Conventional Dual Packer @ 5,612' and 5,616'
Testing Company: Halliburton
Tester: Larry Gibson
Water Cushion: None
IF 15 Minutes: Very Weak Blow
ISI 60 Minutes: --
FF 60 Minutes: No Blow, 0 PSI
FSI 120 Minutes: --
Recovery: 10' Drilling Mud
Bottom Hole Sampler: Pressure - 0 PSI
Recovery - 2,100' cc
Resistivity Data: Drill Pipe Recovery: --
Top: 2.78 @ 83° 1,151 PPM C1
Sampler: 3.21 @ 85° 909 PPM C1
Mud Pit: 1.35 @ 85° 2,424 PPM C1
Pressures: Top Chart (6,040) Bottom Chart (6,040)
IH: 2,005 IH: 2,341
IF: 24 to 24 IF: 67.8 to 65.1
ISI: 24 to 27 ISI: 65.1 to 84.1
FF: 29.8 to 29.8 FF: 84.1 to 70.5
FSI: 29.8 to 32.5 FSI: 70.5 to 28.6
FH: 2,005 FH: 2,028
Top Choke: None Bottom Choke: 3/4"
Bottom Hole Temperature: 120°
Remarks: Mechanically Good Test

DRILL STEM TEST #2

Formation: Desert Creek

Interval: 5,792' to 5,890'

Reason For Test: Gas Kicks And Drill Breaks Within Desert Creek.

Type Test: Conventional DST 2 Packers Set @ 5,786 and 5,792.

Testing Company: Halliburton

Tester: Larry Gibson

Water Cushion: None Used

IF 15 Minutes: Very Weak Blow, Died After 5 Minutes.

ISI 60 Minutes: --

FF 60 Minutes: No Blow

FSI 120 Minutes: --

Recovery: 300' Drilling Mud

Bottom Hole Sampler: Pressure- 0
Recovery - 1,600 ML Drilling Mud

Resistivity Data: Drill Pipe Recovery: --
Top: 1.80 @ 87° 2,000 PPM Cl
Middle: 1.40 @ 88° 2,000 PPM Cl
Bottom: 1.40 @ 89° 1,696 PPM Cl
Sampler: 1.60 @ 86° 1,818 PPM Cl
Mud Pit: 1.80 @ 86° 1,878 PPM Cl

Pressures:	<u>Top Chart (6,040)</u>	<u>Bottom Chart (6,040)</u>
IH:	2838.8	IH: 2871.0
IF:	81.1 to 81.1	IF: 135.6 to 162.7
ISI:	81.1 to 1620.0	ISI: 162.7 to 1677.6
FF:	108.2 to 135.2	FF: 162.0 to 189.8
FSI:	135.2 to 1512.2	FSI: 189.8 to 1596.3
FH:	2784.6	FH: 2843.8

Top Choke: None Bottom Choke: 3/4"

Bottom Hole Temperature: --

Remarks: Mechanically Good Test

5500

5536
ISAPY

5600

LOWER
ISAPY
5630

-10-

5600

LOWER
IS MAY
5630

5700

D SHALE
5730


PRESENT
CREEK
5733

POLE

VOLUME

OK

PER



FILE

12

CALI (IN)		DPHI (2.7)	
6.000	16.00	0.3000	-0.100
GR (GAPI)		NPHI (45)	
0	200.0	0.3000	-0.100

SENSOR MEASURE POINT TO TENSION REFERENCE POINT

NCNL 18.3 FEET -12-
FEFC 2.0 FEET

GR 26.8 FEET
FCNL 19.2 FEET


LITHOLOGY

- 3,500 - 3,600 SILTSTONE - rd brn-brn, m ind, arg, occ sdy, v calc.
- 3,600 - 3,610 SANDSTONE - clr, occ wh, gen fri, f gr, sbang, m srt, calc cmt, p-fr Ø.
- 3,610 - 3,696 SILTSTONE - rd brn-orng/occ gn, m ind, arg, sdy, tr mica.
- 3,696 - 3,706 LIMESTONE - Rd brn-brn, frm, micxl, sl arg, occ anhy.
- 3,706 - 3,720 SANDSTONE - clr, occ wh, fri, f gr, sbang, m srt, calc cmt.
- 3,720 - 4,080 SILTSTONE - rd brn-brn, p-m ind, gen shy, occ sdy, calc cmt.
SHALE - rd brn, sft-frm, blkyl-pty, gen slty, gen calc, occ sdy.
- 4,080 - 4,200 SILTSTONE - rd brn-orng, occ wh, m ind, occ sdy, calc cmt.
SHALE - rd brn, gen frm, blkyl-pty, occ slty, occ calc.
SANDSTONE - clr-ltgy, uncons-fri, f-m gr, sbang, p srt, calc cmt, p Ø.
- 4,200 - 4,370 SHALE - gy-rd brn, sft-frm, blkyl, occ pty, gen slty, calc.
SILTSTONE - gy-brn-rd brn, p-m ind, occ sdy, shy, calc cmt.
- 4,370 - 4,382 SANDSTONE - clr-wh, uncons-fri, f-m gr, sbrnd-sbang, m-p srt, calc cmt, p-fr Ø.
- 4,382 - 4,454 SILTSTONE - gy brn-brn, p-m ind, shy, occ sdy, gen calc.
- 4,454 - 4,696 SILTSTONE - gbrn-brn, occ wh, p-m ind, occ sdy, shy, calc.
SHALE - gy-dkgy, occ brn, blkyl, occ pty, gen slty, calc.
LIMESTONE - wh-ltgy, frm-hd, micxl, arg, gen slty, occ sdy.
- 4,696 - 4,900 LIMESTONE - w - lt gy, frm-hd, micxl, occ crpxl, sl-arg, occ slty.
SILTSTONE - wh-gy, p-m ind, gen sdy, calc cmt, p Ø.
- 4,900-4,920 SHALE - gy-brn-rd brn, frm, blkyl-pty, gen slty, calc.
- 4,920-4,954 SANDSTONE - clr-wh, uncons-fri, m gr, sbang-sbrnd, m srt, calc cmt, p-fr Ø.

LITHOLOGY (CONTINUED)

- 4,954 - 5,066 LIMESTONE - lt gy-gy, occ wh, sft-frm, micxl, gen arg.
SHALE - brn-by, frm-hd, blk occ plty, gen slty, calc.
SHALE - ltbrn-by, occ rdbn, sft-frm, blk-plty, calc.
- 5,098 - 5,186 SHALE - ltbrn-gy, sft-frm, blk-plty, calc.
LIMESTONE - wh-ltgy, frm, occ hd, f-micxl, arg, occ sd.
- 5,186 - 5,260 LIMESTONE - wh-ltgy, sft-frm, blk-plty, calc.
SILTSTONE - gy-brn, m ind, occ w/ calc cmt, p Ø.
- 5,260 - 5,266 SANDSTONE - clr-wh, uncons-fri, vf-f gr, sbang, m-p srt, gen slty, calc cmt, fr-p Ø, NSOFC.
- 5,266 - 5,536 LIMESTONE -wh-ltgy, brn, frm, micxl, gen arg, occ dol, sl slty.
SHALE - gy-gybrn, occ ltgn, frm, plty-blky, slty, calc.
SILTSTONE - clr-w, m ind, occ shy, calc cmt, p Ø.
- 5,536 - 5,560 SANDSTONE - wh-ltgy, uncons-fri, vf gr, sbrnd, m-w srt.
DOLOMITE - w/calc cmt, slty, tr glauc, gen p Ø, NSOFC.
- 5,560 - 5,620 LIMESTONE - dolm, ltgy-dkgy, occ brn, frm, f-micxl, sl arg, p Ø, NSOFC.
- 5,620 - 5,642 SHALE - gy-dkgy, frm-hd, blk, vsly, calc.
- 5,642 - 5,678 LIMESTONE - wh-lt brn, frm, occ hd, f-micxl, arg, occ sd, p Ø, NSOFC.
- 5,678 - 5,734 SHALE - dkgy-blk, gen v sft, occ frm, blk, occ plty, card, calc, occ slty.
- 5,734 - 5,750 ANHYDRITE - wh, sft, mas.
- 5,750 - 5,788 DOLOMITE/LIMESTONE - wh-ltgy, sft-frm, mic-crpxl, arg, gen p Ø, NSOFC.
- 5,788 - 5,832 DOLOMITE - tan, occ brn, sft-frm, mic-crpxl, arg, occ p-fr, intxl Ø, slow wk yel flor cut.
- 5,832 - 5,891 SHALE - dkgy-blk, v sft-sft, blk-plty, occ slty, occ dol, v slow wk yel flor cut.

Typical Minimum BOP Specs (Schematic drawing)



Notes and Auxiliary Equipment

1. All lines, valves and fittings to be minimum 2\"-3000# WP
2. All bolts to be installed and tight.
3. All crew members to be trained in and familiar with BOP equipment, accumulators, and procedures.
4. Hole to be kept full at all times.
5. (a) After nipping up, preventers will pressure tested at 1000 psi for 15 minutes before drilling out.
(b) BOP will be inspected and operated at least daily to insure good working order.
(c) All pressure and operating tests will be recorded on daily drilling report.
6. An upper kelly cock will be used at all times.
7. A drill pipe float will be available at all times for use when penetrating formations with anticipated abnormal pressures.
8. Mud system monitoring method: Visual
9. A 3000 psi WP full opening valve, properly subbed w/DP pin, will be available on the floor at all times.

ENVIRONMENTAL IMPACT SURFACE USE AND
OPERATIONS PLAN FOR FEDERAL LEASES

MOSBACHER PRODUCTION CO.
NE SW SECTION 24, T 39 N, R 21 E
SAN JUAN COUNTY, UTAH
LEASE NO. UTAH 21253

The following data is submitted herewith to supplement Application For Permit to Drill the captioned well:

1. EXISTING ROADS Refer to MAP A (Shown in RED)

- A. Proposed well site as staked. (Actual staking should include two each 200-foot reference stakes.)

The proposed well is staked and the surveyor's plat is attached.

- B. Route and distance from nearest town or locatable reference point to where access route leaves main road.

Travel north of Bluff on Highway 163 approximately 6.5 miles. Turn left on existing dirt road and travel 3.5 miles west to the location.

- C. Access road to location color coded or labeled.

Refer to Map A shown in RED.

- D. If exploratory, show existing roads within a three mile radius (including type of surface conditions, etc.).

Existing roads within a three mile radius are shown on Map A. The existing roads are dirt.

- E. If development, show existing roads within one mile radius of well site.

N/A

- F. Plans for improvement and/or maintenance of existing roads.

There are no plans to improve existing roads, but they will be maintained as necessary, flat blading existing trail to location.

2. PLANNED ACCESS ROADS (Map showing necessary access roads to be constructed or reconstructed, showing:)

Refer to Map A (Shown in GREEN)

1. Width - 18'
2. Maximum grade - 4% or less
3. Turn out - None required
4. Drainage design - No ditching will be required for drainage during the drilling of this well
5. Location and size of culverts and brief description of any major cuts and fills- There will be no major cut or fills and no culverts will be necessary.
6. Surface material - None required
7. Necessary gates, cattleguards or fence cuts - None required.
8. New or reconstructed roads are to be center-line flassed at time of location staking- Center line of the proposed road is flassed.

3. LOCATION OF EXISTING WELLS: Refer to Exhibit #1

Two-mile radius map if exploratory, or 1-mile radius map if development well, showing and identifying existings:

1. Water wells - 0
2. Abandon wells - 1
3. Temporarily abandoned wells - 0
4. Disposal wells - 0
5. Drilling wells - 0
6. Producing wells - 0
7. Shut-in wells - 0
8. Injection wells - 0
9. Monitoring or observation wells or other resources - 0

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES.

A. Within one mile radius of location showing the following existings facilities owned or controlled by lessee operator.

1. Tank batteries - 0
2. Production facilities - 0

3. Oil gathering lines - 0
4. Gas gathering lines - 0
5. Injection lines - 0
6. Disposal lines - (note if lines are buried) N/A

B. New facilities contemplated in the event of production show:

Refer to Exhibit #2

1. Proposed location and attendant lines by flassing, if off well pad - All facilities will be located on the drill pad but will not be placed on fill.
2. Dimensions of facilities - Production facilities will require an area of approximately 150' x 300'.
3. Constructed methods and material - Pumping unit only will be built on the existing drill pad. No Federal or Indian lands will be disturbed for construction materials.
4. Protective measures and devices to protect livestock

Fences will be installed around all facilities.

C. Plan for rehabilitation of disturbed areas no longer needed for operations after construction completed:

Rehabilitation of disturbed areas no longer needed for operation will be accomplished by grading, leveling and seeding as recommended by the B.L.M.

5. LOCATION AND TYPE OF WATER SUPPLY Refer to Map A (Shown in BLUE).

- A. Location and type of water supply either on map or by written description.

Water will be trucked to the location from a private pond just outside of Bluff, Utah.

- B. State method of transporting water and show any roads or pipelines needed.

Water will be trucked-see Map 'A'

- C. If water well is to be drilled on lease, so state:

No water well will be required.

6. SOURCE OF CONSTRUCTION MATERIALS

- A. Show information either on map or by written description:

If any construction materials are required they will be obtained from private sources. No material obtained from Federal or Indian Lands.

- B. Identify if from Federal land.

Dirt will be from private sources.

- C. Describe where materials such as sand, gravel, stone and soil material are to be obtained and used:

Materials such as sand, gravel or stone, if required, will be obtained from private source. No Federal or Indian Land involved.

- D. Show any needed access roads crossing Federal or Indian lands under Item 2:

No access road for construction materials will be necessary.

7. METHODS FOR HANDLING WASTE DISPOSAL

Describe methods and location of proposed containment and disposal of waste material, including:

1. Cuttings -Drill cuttings separated from the mud will be contained in the reserve pit.

2. Drilling fluids

Drilling fluids will be contained in the mud tanks and in a reserve pit. The reserve pit will be fenced on three sides during drilling operations with woven wire and two strands of barb wire on top.

3. Produced fluids (oil, water)

Produced fluids, both oil and water will be contained in a test tank.

4. Sewage - A portable chemical toilet will be provided.

5. Garbage and other waste material should be fenced with mesh wire.

A fenced pit will be provided for trash. The pit will be completely enclosed with small mesh wire.

6. Statement regarding cleanup of well site area when rig moves out.

As soon as the rig moves out the area will be cleaned of all trash and materials and the fourth side of the pit fenced. The location and the reserve pit be leveled and restoration work will begin as soon as possible.

8. AUXILIARY FACILITIES

Identify all proposed camps and air strips on a map as to their location, area required, and construction methods:

No camps or airstrips will be constructed.

9. WELL SITE LAYOUT A plat not less than 1" = 50' showing:

1. Cross Section of drill pad with cuts and fills
Refer to Exhibit #3
2. Location of mud tanks, reserve, burn and trash pits, pipe racks, living facilities, and soil stockpiles.
Refer to Exhibit #2
3. Rig orientation, parking areas and access roads.
Refer to Exhibit #2
4. Statement as to whether pits are to be lined or unlined.

The pits will be lined with plastic.

10. PLANS FOR RESTORATION OF SURFACE

State restoration program upon completion of operations including:

1. Backfilling, leveling, contouring and waste disposal, segregation of spoils materials as needed.

Pits will be allowed to dry and will be backfilled and contoured to as near the original topography as is possible and then reseeded.

Spoils material will be segregated and burned, hauled away or burned as soon as possible after the operations have ceased.

2. Revegetation and rehabilitation - including access roads.
(Normally per BLM recommendations)

Revegetation will be achieved by seeding with a mixture as required by the B.L.M., including the access road if required.

3. Prior to rig release, pits will be fenced and so maintained until clean-up.

Prior to rig release, the pits will be fenced on all four sides and will be so maintained until restoration work is initiated.

4. If oil on pit, remove oil or install overhead flassings.

The oil in the pit will be removed, or if this isn't possible, overhead flassings will be installed.

5. Time table for commencement and completion of rehabilitation operations.

Rehabilitation operations will begin as soon as practical after the rig is off location and should be completed by Spring 1982.

11. OTHER INFORMATION General description of:

1. Topography, soil characteristics, geological features, flora and fauna.

Refer to Archeological Report.

2. Other surface use activities and surface ownership of all involved land.

The surface is used for livestock grazing.
Surface owner: B.L.M.

3. Proximity of water, occupied dwellings, archeological, historical or cultural sites.

The general drainage is south to the San Juan River. There are no occupied dwellings, archeological, historical or cultural sites visible on or near the location. The nearest occupied dwelling is approximately 6.5 miles to the south.

12. LESEE'S OR OPERATOR'S REPRESENTATIVE:

Mr. Don Green
Operations Manager
Mosbacher Production Co.
Suite 2100
Capital National Bank Bldg.
Houston, Tx. 77002

Allen, Bludworth & Crouch
P.O. Box 976
Casper, WY. 82602
307 234 0592
307 234 3571
L.E. Bludworth*
B.W. Allen*

*Contact for Pre-drill Inspection

13. CERTIFICATION:


I hereby certify that I or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Mosbacher Production Co. and its contractors and sub-contractors in conformity with this plan and terms and conditions under which it is approved.

B.W. Allen

6/22/81

Date

SKETCH FOR NO. 1





PRODUCTION, RIG AND FRAC LAYOUT

EXHIBIT #2

W.A.A.
L.E.B.
6-17-81

SEASCHER PRODUCTION CO.



SCALE: 1" = 50' HOR. & 1" = 20' VERT.

EXHIBIT #3

STIPULATIONS

Well sign should read:

Mosbacher Production Co.

U-21253 U-16555

No. 1-24 Federal No. 26-1 FEDERAL

NESW 24-39S-21E

NE NE 26 - 39S - 21E

San Juan County, Utah

Construction:

1. The operator or his contractor will contact the San Juan Resource Area Office in Monticello, Utah (Phone (801) 587-2201) 48 hours prior to beginning any work on public land.
2. The dirt contractor will be furnished with a copy of the Surface Use Plan and any additional BLM stipulations prior to any work.
3. The San Juan County Road Department in Monticello will be contacted prior to the use of county roads for this activity, Mr. Dick Traister at (801) 587-2249.
4. If subsurface cultural material is exposed during construction, work in that spot will stop immediately and the San Juan Resource Area Office will be contacted. All employees working in the area will be informed by the operator that they will be subject to prosecution if they are caught disturbing archaeological sites or picking up artifacts. Salvage or excavation of identified archaeological sites will only be done if damage occurs.
5. Surfacing material will not be placed on the access road or location without prior BLM approval.
6. The top 10 inches of soil material will be removed from the location and stockpiled on the west side of the location. Topsoil along the access will be reserved in place.
7. A burning permit will be required before burning trash between May 1 and October 31. This can be acquired by contacting the State Fire Warden, John Baker at (801) 587-2705.

Rehabilitation

1. The operator or his contractor will contact the San Juan Resource Area BLM office in Monticello, Utah, phone (801) 587-2201, 48 hours prior to starting rehabilitation work that involves earthmoving equipment and upon completion of restoration measures.
2. All disturbed areas will be recontoured to blend as nearly as possible with the natural topography.
3. The stockpiled topsoil will be evenly distributed over the disturbed area.
4. All disturbed areas will be scarified with the contour to a depth of 10 inches.
6-8
5. Seed will be (broadcast) at a time to be specified by the BLM with the following seed prescription. When broadcast seeding, a harrow or some such implement will be dragged over the seeded area to assure seed cover.

<u>3</u> lbs/acre	Indian ricegrass (<i>Oryzopsis hymenoides</i>)
<u>2</u> lbs/acre	Fourwing saltbush (<i>Atriplex canescens</i>)
<u>2</u> lbs/acre	Sand dropseed (<i>Sporobolus cryptandrus</i>)

Curly grass

Production

1. The reserve pit and that portion of the location and access road not needed for production or production facilities will be reclaimed in the methods described in the rehabilitation section. Enough topsoil will be retained to reclaim the remainder of the location at a future date. The remaining stockpile of topsoil will be seeded in place using the prescribed seed mixture.
2. All above-ground production facilities will be painted a neutral color to be approved by the BLM.
3. The access shall be upgraded to the following specifications:

Ditch and crown to 18 feet total width. Culvert will be installed if necessary.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See other in-
structions on
reverse side)Form approved.
Budget Bureau No. 42-R355.5.

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input checked="" type="checkbox"/> Other _____				5. LEASE DESIGNATION AND SERIAL NO. UTAH 21253	
b. TYPE OF COMPLETION: NEW WELL <input type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other <u>EXPLORATORY</u>				6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A	
2. NAME OF OPERATOR MOSBACHER PRODUCTION CO.				7. UNIT AGREEMENT NAME N/A	
3. ADDRESS OF OPERATOR 1300 Main St., Suite 2100, Houston, Tx 77002				8. FARM OR LEASE NAME Federal	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements) At surface 1980' FWL 7 1980' FSL; NE SW, Sec. 24, T39S-R21E At top prod. interval reported below At total depth SAME				9. WELL NO. 1-24	
14. PERMIT NO. N/A				12. COUNTY OR PARISH San Juan	
15. DATE SPURRED 7/21/81				13. STATE Utah	
16. DATE T.D. REACHED 8/15/81		17. DATE COMPL. (Ready to prod.) 8/18/81 P&A		18. ELEVATION OF, RKB, RT, GR, ETC.* OIL, GAS & MINING DIVISION OF 4716, DP 4715, GL4703	
20. TOTAL DEPTH, MD & TVD 5890' MD		21. PLUG, BACK T.D., MD & TVD Surface		19. ELEV. CASINGHEAD ---	
22. IF MULTIPLE COMPL., HOW MANY* ---				23. INTERVALS DRILLED BY ROTARY TOOLS CABLE TOOLS 10-5890'	
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* ---				25. WAS DIRECTIONAL SURVEY MADE No	
26. TYPE ELECTRIC AND OTHER LOGS RUN Compensated Neutron Form. Density; Ind. SFL				27. WAS WELL CORED No	
28. CASING RECORD (Report all strings set in well)					
CASING SIZE		WEIGHT, LB./FT.		DEPTH SET (MD)	
13-3/8"		48#		205'	
9-5/8"		36#		1768'	
29. LINER RECORD					
SIZE		TOP (MD)		BOTTOM (MD)	
30. TUBING RECORD					
SIZE		DEPTH SET (MD)		PACKER SET (MD)	
31. PERFORATION RECORD (Interval, size and number)					
32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.					
DEPTH INTERVAL (MD)			AMOUNT AND KIND OF MATERIAL USED		
33.* PRODUCTION					
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)			WELL STATUS (Producing or shut-in)
DATE OF TEST		HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.
FLOW. TUBING PRESS.		CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)					TEST WITNESSED BY
35. LIST OF ATTACHMENTS DST's, Geological Report, Logs.					
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records					
SIGNED <u>Beverly A. Dausin</u>		TITLE <u>Engineering Asst.</u>		DATE <u>10/9/81</u>	
(Beverly A. Dausin)					

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES:				38. GEOLOGIC MARKERS		
SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION TEST, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURE, AND RECOVERIES				NAME	TOP	
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.		MEAS. DEPTH	TRUE VERT. DEPTH
			(SEE ATTACHED)	(SEE ATTACHED)		

LITHOLOGY

- 3,500 - 3,600 SILTSTONE - rd brn-brn, m ind, arg, occ sdy, v calc.
- 3,600 - 3,610 SANDSTONE - clr, occ wh, gen fri, f gr, sbang, m srt, calc cmt, p-fr Ø.
- 3,610 - 3,696 SILTSTONE - rd brn-orng/occ gn, m ind, arg, sdy, tr mica.
- 3,696 - 3,706 LIMESTONE - Rd brn-brn, frm, micxl, sl arg, occ anhy.
- 3,706 - 3,720 SANDSTONE - clr, occ wh, fri, f gr, sbang, m srt, calc cmt.
- 3,720 - 4,080 SILTSTONE - rd brn-brn, p-m ind, gen shy, occ sdy, calc cmt.
SHALE - rd brn, sft-frm, blkyl-pty, gen slty, gen calc, occ sdy.
- 4,080 - 4,200 SILTSTONE - rd brn-orng, occ wh, m ind, occ sdy, calc cmt.
SHALE - rd brn, gen frm, blkyl-pty, occ slty, occ calc.
SANDSTONE - clr-ltgy, uncons-fri, f-m gr, sbang, p srt, calc cmt, p Ø.
- 4,200 - 4,370 SHALE - gy-rd brn, sft-frm, blkyl, occ pty, gen slty, calc.
SILTSTONE - gy-brn-rd brn, p-m ind, occ sdy, shy, calc cmt.
- 4,370 - 4,382 SANDSTONE - clr-wh, uncons-fri, f-m gr, sbrnd-sbang, m-p srt, calc cmt, p-fr Ø.
- 4,382 - 4,454 SILTSTONE - gy brn-brn, p-m ind, shy, occ sdy, gen calc.
- 4,454 - 4,696 SILTSTONE - gbrn-brn, occ wh, p-m ind, occ sdy, shy, calc.
SHALE - gy-dkgy, occ brn, blkyl, occ pty, gen slty, calc.
LIMESTONE - wh-ltgy, frm-hd, micxl, arg, gen slty, occ sdy.
- 4,696 - 4,900 LIMESTONE - w - ltgy, frm-hd, micxl, occ crpxl, sl-arg, occ slty.
SILTSTONE - wh-gy, p-m ind, gen sdy, calc cmt, p Ø.
- 4,900-4,920 SHALE - gy-brn-rd brn, frm, blkyl-pty, gen slty, calc.
- 4,920-4,954 SANDSTONE - clr-wh, uncons-fri, m gr, sbang-sbrnd, m srt, calc cmt, p-fr Ø.

FLUID SAMPLE DATA				Date 8-16-81		Ticket Number 981706	
Sampler Pressure <u>30</u> P.S.I.G. at Surface Recovery: Cu. Ft. Gas <u>0</u> cc. Oil <u>0</u> cc. Water <u>0</u> cc. Mud <u>1600 ML</u> Tot. Liquid cc. _____				Kind of D.S.T. <u>OPEN HOLE</u>		Halliburton Location <u>FARMINGTON</u>	
Gravity _____ ° API @ _____ °F. Gas/Oil Ratio _____ cu. ft./bbl.				Tester <u>LARRY GIBSON</u>		Witness _____	
RESISTIVITY _____ CHLORIDE CONTENT _____ Recovery Water _____ @ _____ °F. _____ ppm Recovery Mud _____ @ _____ °F. _____ ppm Recovery Mud Filtrate _____ @ _____ °F. _____ ppm Mud Pit Sample <u>1.80</u> @ <u>76</u> °F. _____ ppm Mud Pit Sample Filtrate _____ @ _____ °F. _____ ppm Mud Weight <u>9.5</u> vis <u>50</u> sec.				Drilling Contractor <u>ARAPHOE # 6</u>		IC-dr	
EQUIPMENT & HOLE DATA							
Formation Tested <u>Desert Creek</u>				Elevation <u>4703' GR-4716' KB</u> Ft.			
Net Productive Interval _____				Ft.			
All Depths Measured From <u>4716' KB</u>				Total Depth <u>5890'</u> Ft.			
Main Hole/Casing Size <u>8 3/4"</u>				Drill Collar Length <u>468'</u> I.D. <u>2 1/4"</u>			
Drill Pipe Length <u>5288'</u> I.D. <u>3.826"</u>				Packer Depth(s) <u>5786'-5792'</u> Ft.			
Depth Tester Valve <u>5763.5'</u>				Ft.			
TYPE		AMOUNT		Depth Back Pres. Valve		Surface Choke	
Cushion						Bottom Choke <u>3/4"</u>	
Recovered		<u>300</u>		Feet of drilling mud			
Recovered				Feet of TOP SAMPLE <u>1.40</u> Res. @ <u>89</u> °F.			
Recovered				Feet of MIDDLE SAMPLE <u>1.40</u> @ <u>85</u> °F			
Recovered				Feet of BOTTOM SAMPLE <u>1.66</u> @ <u>85</u> °F.			
Recovered				Feet of			
Remarks <u>SEE PRODUCTION TEST DATA SHEET</u>							
<u>*-See attached incremental pressure sheet</u>							
TEMPERATURE		Gauge No. <u>6040</u>		Gauge No. <u>6039</u>		Gauge No. _____	
Depth:		<u>5768.5</u> Ft.		<u>5885.5</u> Ft.		Ft.	
Est. _____ °F.		24 Hour Clock		24 Hour Clock		Hour Clock	
Blanked Off <u>No</u>		Blanked Off <u>Yes</u>		Blanked Off _____		Tool Opened <u>05:53</u>	
Actual <u>120</u> °F.		Pressures		Pressures		Pressures	
	Field	Office	Field	Office	Field	Office	Reported Minutes
Initial Hydrostatic	<u>2838.8</u>	<u>2816.3</u>	<u>2871.0</u>	<u>2869.8</u>			Computed Minutes
First Period Flow	Initial	<u>81.8</u>	<u>70.8</u>	<u>135.6</u>	<u>125.5</u>		
	Final	<u>81.8</u>	<u>87.4</u>	<u>162.7</u>	<u>144.4</u>	<u>15</u>	<u>*</u>
	Closed in	<u>1620.0</u>	<u>1611.6</u>	<u>1677.6</u>	<u>1672.5</u>	<u>60</u>	<u>*</u>
Second Period Flow	Initial	<u>108.2</u>	<u>113.1</u>	<u>162.7</u>	<u>166.3</u>		
	Final	<u>135.2</u>	<u>124.6</u>	<u>189.8</u>	<u>185.0</u>	<u>60</u>	<u>*</u>
	Closed in	<u>1512.2</u>	<u>1541.1</u>	<u>1596.3</u>	<u>1608.1</u>	<u>120</u>	<u>*</u>
Third Period Flow	Initial						
	Final						
Final Hydrostatic	<u>2784.6</u>	<u>2793.8</u>	<u>2843.8</u>	<u>2850.7</u>			

Legal Location Sec. - Twp. - Rng. 24-39S-21E

Field Area WILDCAT

County SAN JUAN

State UTAH

FEDERAL

1-24

2

5792-5890'

MOSBACHER PRODUCTION COMPANY

Casing perms. _____		Bottom choke _____		Surf. temp. _____ °F		Ticket No. 981706	
Gas gravity _____		Oil gravity _____		GOR _____			
Spec. gravity _____		Chlorides _____		ppm Res. _____		@ _____ °F	
INDICATE TYPE AND SIZE OF GAS MEASURING DEVICE USED							

Date Time	a.m. p.m.	Choke Size	Surface Pressure psi	Gas Rate MCF	Liquid Rate BPD	Remarks
8-15-81						On location
2100						
0015						Picked up and made up tools
0100						Went in hole with tools
0551						ON bottom
0553		BH				Opened tool
0555		"				Very, very weak blow
0600		"				No blow at surface
0605		"				"
0608						Closed tool
0708						Opened tool
0713						No blow at surface
0718						"
0723						"
0728						"
0733						"
0733						"
0738						"
0743						"
0748						"
0753						"
0758						"
0803						"
0808						Closed tool
1008						Opened bypass and tool out of hole.
						Out of hole.

MOSBACHER PRODUCTION COMPANY
Lease Owner/Company Name

98-1706
Ticket Number

B.T. 6040

B.T. 6039

B.T.

Depth 5768

Depth 5885

Depth

Time (minutes)	Log 1 - 11 (1)	PSIG Temp Corr	Time (minutes)	Log 1 - 11 (1)	PSIG Temp Corr	Time (minutes)	Log 1 - 11 (1)	PSIG Temp Corr
FIRST FLOW			FIRST FLOW					
0		70.8	0		125.5			
3		71.9	3		130.4			
6		76.1	6		134.0			
9		80.0	9		137.1			
12		83.4	12		141.2			
14.3		87.4	14.7		144.4			
FIRST CIP			FIRST CIP					
0		87.4	14.7		144.4			
5		137.2	5		196.2			
10		207.0	10		260.2			
15		310.0	15		360.4			
20		457.4	20		510.7			
25		655.7	25		705.4			
30		859.7	30		915.8			
35		1050.5	35		1105.7			
40		1212.3	40		1266.8			
45		1347.8	45		1403.4			
50		1460.4	50		1520.5			
55		1558.6	55		1617.8			
53.3		1611.6	58.5		1672.5			
SECOND FLOW			SECOND FLOW					
0		113.1	0		166.3			
10		113.6	10		170.5			
20		114.5	20		173.6			
30		116.6	30		175.5			
40		118.8	40		178.9			
50		121.6	50		181.0			
64.0		124.6	64.2		185.0			
SECOND CIP			SECOND CIP					
0		124.6	0		185.0			
10		151.2	10		218.7			
20		189.5	20		258.9			
30		240.9	30		311.8			
40		313.8	40		335.6			
50		409.7	50		437.8			
60		550.8	60		631.9			
70		737.6	70		819.1			
80		948.9	80		1027.4			
90		1146.8	90		1225.8			
100		1320.5	100		1396.4			
110		1454.7	110		1531.7			
118.3		1541.1	117.3		1608.1			



	O. D.	I. D.	LENGTH	DEPTH
Drill Pipe or Tubing	4 1/2"	3.826"	5288'	
Drill Collars	6"	3"	375'	
Reversing Sub	5 3/4"	3"	1'	5663.5'
Water Cushion Valve				
Drill Pipe				
Drill Collars	6"	2 1/4"	93'	
Handling Sub & Choke Assembly	5 3/4"	3 1/2"	1'	
Dual CIP Valve	5"	.75"	6'	5757.5'
Dual CIP Sampler	5"	.75"	5'	5763.5'
Hydro-Spring Tester				
Multiple CIP Sampler				
Extension Joint				
AP Running Case	5"	3"	4'	5768.5'
Hydraulic Jar	5"	1.75"	5'	
VR Safety Joint	5"	1"	3'	
Pressure Equalizing Crossover				
Packer Assembly	7 3/4"	1.53"	6'	5786.5'
Distributor				
Packer Assembly	7 3/4"	1.53"	6'	5792'
	5 3/4"	3 1/2"	1' Change over	
	6"	2 1/4"	62' Drill Collars	
Flush Joint Anchor				
Pressure Equalizing Tube				
	5 3/4"	3 1/2"	1' Change over	
Blanked-Off B.T. Running Case				
Drill Collars				
Anchor Pipe Safety Joint				
Packer Assembly				
Distributor				
Packer Assembly				
Anchor Pipe Safety Joint				
Side Wall Anchor				
Drill Collars				
Flush Joint Anchor	5 3/4"	3 1/2"	27'	
Blanked-Off B.T. Running Case	5 3/4"	2 1/2"	4.5'	5885.5'
Total Depth				5890'

Casing perms. _____		Bottom choke _____		Surf. temp. _____		Ticket No. 981705	
Gas gravity _____		Oil gravity _____		GOR _____			
Spec. gravity _____		Chlorides _____		ppm Res. _____		@ _____ °F	
INDICATE TYPE AND SIZE OF GAS MEASURING DEVICE USED							
Date Time	a.m. p.m.	Choke Size	Surface Pressure psi	Gas Rate MCF	Liquid Rate BPD	Remarks	
0126						On location.	
0415						Picked up and made up tool.	
0600						Went in hole with tools.	
0819						On bottom with tools.	
0843						Opened tools.	
0844		Bubble Hose				Very weak blow.	
0848		"				Still very weak blow on surface only.	
0851		"				"	
0857		"				Closed tool.	
0957		"				Opened tool with no blow at surface.	
1002		"				No blow at surface.	
1008		"				"	
1015		"				"	
1025		"				"	
1030		"				"	
1040		"				"	
1050		"				"	
1055		"				"	
1057		"				Closed tool.	
1257		"				Opened bypass and came out of hole.	
1700						Out of hole.	

	O. D.	I. D.	LENGTH	DEPTH
Drill Pipe or Tubing				
Drill Collars				
Reversing Sub				
Water Cushion Valve				
Drill Pipe	4.50"	3.826"	5112'	
Drill Collars	6.00"	2.25"	468'	
Handling Sub & Choke Assembly X Over	5.75"	3.50"	1.00'	5582'
Dual CIP Valve				
Dual CIP Sampler	5.00"	.75"	6.00'	5583.4'
Hydro-Spring Tester	5.00"	.75"	5.00'	5589.4'
Multiple CIP Sampler				
Extension Joint				
AP Running Case	5.00"	3.00"	4.1'	5594.4'
Hydraulic Jar	5.00"	1.75"	5.00'	
VR Safety Joint	5.00"	1.00"	3.00'	
Pressure Equalizing Crossover				
Packer Assembly	7.75"	1.53"	6.00'	5610.5'
Distributor				
Packer Assembly	7.75"	1.53"	6.00'	5615.5'
Flush Joint Anchor				
Pressure Equalizing Tube				
Blanked-Off B.T. Running Case				
Drill Collars				
Anchor Pipe Safety Joint				
Packer Assembly				
Distributor				
Packer Assembly				
Anchor Pipe Safety Joint X Over	5.75"	3.50"	1.00'	
Side Wall Anchor Drill Collars	6.00"	2.25"	62'	
Drill Collars X Over	5.75"	3.50"	1.00'	
Flush Joint Anchor	5.75"	3.50"	10'	
Blanked-Off B.T. Running Case	5.75"	2.50"	4.50'	5690.5'
Total Depth				5695'

**UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY**

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☐ other ☐ Dry Hole
2. NAME OF OPERATOR
Mosbacher Production Co.
3. ADDRESS OF OPERATOR
1300 Main St., Suite 2100, Houston, Tx 77002
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1980' FWL & 1980' FSL NE SW, Sec. 24
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH: Same

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) <u>Location Clean-up.</u>	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

This well was plugged and abandoned on 8/18/81. On January 18, 1982, the location was cleaned up with the required location marker in place and ready for inspection.

Subsurface Safety Valve: Manu. and Type Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Beverly A. Dausin TITLE Engineering Asst. DATE 7/29/82

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

5. LEASE Utah 21253	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A	
7. UNIT AGREEMENT NAME N/A	
8. FARM OR LEASE NAME Federal	
9. WELL NO. 1-24	
10. FIELD OR WILDCAT NAME Wildcat	
11. SEC., T., R., M. OR BLK. AND SURVEY OR AREA Sec. 24 T39S R21E	
12. COUNTY OR PARISH San Juan	13. STATE Utah
14. API NO. N/A	
15. ELEVATIONS (SHOW DE, KDB, AND WD) GL 4703', DE 4715', KB 4716'	

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES:

SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	38. GEOLOGIC MARKERS		
				NAME	MEAS. DEPTH	TRUE VERT. DEPTH
			(SEE ATTACHED)	(SEE ATTACHED)		

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☐ other ☐ Dry Hole
2. NAME OF OPERATOR
Mosbacher Production Co.
3. ADDRESS OF OPERATOR
1300 Main St., Suite 2100, Houston, Tx 77002
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1980' FWL & 1980' FSL NE SW, Sec. 24
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH: Same

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) Location Clean-up.	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, including estimated date of starting any proposed work. If well is being plugged, include measured and true vertical depths for all markers and zones pertaining to the work.)

This well was plugged and abandoned on 8/1/82. The well was plugged with cement and the location was cleaned up with the required location marker. The well is ready for inspection.

Subsurface Safety Valve: Manu. and Type _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Beverly A. Dausin TITLE Engineering Asst. DATE _____

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

5. LEASE Utah	6. IF INDIAN, AGENCY OR TRIBAL NAME N/A	7. UNIT AGREEMENT NAME N/A	8. FARM OR LEASE NAME Federal	9. WELL NO. 1-24	10. FIELD OR WELL NAME Wildcat	11. SEC., T., R., AND BLK. AND AREA Sec. 24	12. COUNTY OR PRINCIPALITY San Juan	13. STATE Utah	14. API NO. N/A	15. ELEVATIONS (FEET OR METERS) (GL 4703', K 15', K 16')
------------------	--	-------------------------------	----------------------------------	---------------------	-----------------------------------	--	--	-------------------	--------------------	--

(NOTE: Report results of multiple completions or zone change on Form 9-330.)

RECEIVED
FEB 02 1983
DIVISION OF
OIL, GAS & MINING